

PARKING LOT OF SAN JOSÉ (CÁDIZ)

On July 10th 2000, the Company together with the city council of Cadiz signed the concession for the construction and subsequent exploitation of the parking lot placed at *Plaza de Jesus de la Paz*. Nowadays, the works for the construction of this parking lot have been completed. The grand opening took place on February 14th, 2003.

The construction area of the said parking is 12.000 m², with a system to undertake of slurry walls perimeter 80cm thick and 18m depth. These walls are fixed to the subsoil with a row anchorage system between 20 and 30 meters and 30% slope. The emptying of the site is done up to level of -11.5, being the slab under a pressure of 6.5 atmospheres.

PARKING CONSTRUCTION FIGURES:

- **Earthworks** **46000 m³**
- **Drainage** **250 Hm³ - 300 l/s**
- **Concrete used** **15000 m³**
- **Iron used** **1700 Tm**
- **Workforce** **200**
- **Project deadline** **15 months**